





Technical Parameters

Buffer diameter	Ø65	mm
Buffer height	80	mm
Stroke (max. deflection)	60	mm
Energy capacity	0.265	kNm
Max. buffer force	28	kN
Base plate	100 sq x 8 thk	mm
Mounting holes	4 x Ø12 on 70 sq	mm
Buffer material	Polyurethane foam	
Base plate material	MS, painted	

NOTES

1. General arrangement for customer approval - not for manufacture.
2. Dashed line = striker face at maximum deflection.
3. Polyurethane (PU) foam buffer, shown in red, bonded to MS base plate; 4-bolt mounting.
4. Grooved profile controls the deflection characteristic; groove pattern per Adoni Tech design.
5. Operating temperature -20 to +80 °C.
6. Selection: www.cranebuffer.com | impactcal.netlify.app

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS GENERAL ARRANGEMENT - OUTLINE ONLY DIMENSIONS SUBJECT TO CHANGE WITHOUT PRIOR NOTICE PROJECTION: FIRST ANGLE				FINISH: PU red / plate painted		DEBUR AND BREAK SHARP EDGES		DO NOT SCALE DRAWING		REVISION A					
adoniTech ADONI TECH Addl. MIDC, Kodoli, Satara 415004 www.adonitech.co.in								TITLE:							
								JHQ-C-1 POLYURETHANE FOAM CRANE BUFFER - GA							
												DWG NO.		A4	
												AT/GA/JHQC/1			
MATERIAL: PU foam, MS base plate		WEIGHT:		SCALE: 1:2.5		SHEET 1 OF 1									