





Technical Parameters

Buffer diameter	Ø160	mm
Buffer height	160	mm
Stroke (max. deflection)	120	mm
Energy capacity	3.125	kNm
Max. buffer force	169	kN
Base plate	200 sq x 10 thk	mm
Mounting holes	4 x Ø18 on 160 sq	mm
Buffer material	Polyurethane foam	
Base plate material	MS, painted	

NOTES

1. General arrangement for customer approval - not for manufacture.
2. Dashed line = striker face at maximum deflection.
3. Polyurethane (PU) foam buffer, shown in red, bonded to MS base plate; 4-bolt mounting.
4. Grooved profile controls the deflection characteristic; groove pattern per Adoni Tech design.
5. Operating temperature -20 to +80 °C.
6. Selection: www.cranebuffer.com | impactcal.netlify.app

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS GENERAL ARRANGEMENT - OUTLINE ONLY DIMENSIONS SUBJECT TO CHANGE WITHOUT PRIOR NOTICE PROJECTION: FIRST ANGLE		FINISH: PU red / plate painted		DEBUR AND BREAK SHARP EDGES		DO NOT SCALE DRAWING		REVISION A	
						 ADONI TECH Addl. MIDC, Kodoli, Satara 415004 www.adonitech.co.in			
	NAME		SIGNATURE		DATE	JHQ-C-11 POLYURETHANE FOAM CRANE BUFFER - GA DWG NO. AT/GA/JHQC/11			
DRAWN	PARESH ADAVANI				07-09-22				
CHK'D									
APPV'D	PARESH ADAVANI				09-09-22				
MFG									
Q.A						A4			
MATERIAL: PU foam, MS base plate			WEIGHT:			SCALE: 1:5		SHEET 1 OF 1	