





PU BUFFER - BASE PLATE MOUNT



VIEW FROM STRIKER END

Technical Parameters

Buffer diameter	Ø250	mm
Buffer height	320	mm
Stroke (max. deflection)	240	mm
Energy capacity	15.7	kNm
Max. buffer force	414	kN
Base plate	320 sq x 12 thk	mm
Mounting holes	4 x Ø22 on 250 sq	mm
Buffer material	Polyurethane foam	
Base plate material	MS, painted	

NOTES

- General arrangement for customer approval - not for manufacture.
- Dashed line = striker face at maximum deflection.
- Polyurethane (PU) foam buffer, shown in red, bonded to MS base plate; 4-bolt mounting.
- Grooved profile controls the deflection characteristic; groove pattern per Adoni Tech design.
- Operating temperature -20 to +80 °C.
- Selection: www.cranebuffer.com | impactcal.netlify.app

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS GENERAL ARRANGEMENT - OUTLINE ONLY DIMENSIONS SUBJECT TO CHANGE WITHOUT PRIOR NOTICE PROJECTION: FIRST ANGLE		FINISH: PU red / plate painted		DEBUR AND BREAK SHARP EDGES		DO NOT SCALE DRAWING		REVISION A		
						adoniTech		ADONI TECH Addl. MIDC, Kodoli, Satara 415004 www.adonitech.co.in		
	NAME		SIGNATURE		DATE		TITLE: JHQ-C-18 POLYURETHANE FOAM CRANE BUFFER - GA			
DRAWN	PARESH ADAVANI				21-09-22					
CHK'D							DWG NO. AT/GA/JHQC/18			
APPV'D	PARESH ADAVANI				23-09-22					
MFG							A4			
Q.A										
MATERIAL: PU foam, MS base plate			WEIGHT:			SCALE: 1:8		SHEET 1 OF 1		