





Technical Parameters

Buffer diameter	Ø320	mm
Buffer height	320	mm
Stroke (max. deflection)	240	mm
Energy capacity	25.732	kNm
Max. buffer force	675	kN
Base plate	400 sq x 14 thk	mm
Mounting holes	4 x Ø22 on 315 sq	mm
Buffer material	Polyurethane foam	
Base plate material	M5, painted	

NOTES

1. General arrangement for customer approval - not for manufacture.
2. Dashed line = striker face at maximum deflection.
3. Polyurethane (PU) foam buffer, shown in red, bonded to MS base plate; 4-bolt mounting.
4. Grooved profile controls the deflection characteristic; groove pattern per Adoni Tech design.
5. Operating temperature -20 to +80 °C.
6. Selection: www.cranebuffer.com | impactcal.netlify.app

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS GENERAL ARRANGEMENT - OUTLINE ONLY DIMENSIONS SUBJECT TO CHANGE WITHOUT PRIOR NOTICE PROJECTION: FIRST ANGLE		FINISH: PU red / plate painted		DEBUR AND BREAK SHARP EDGES		DO NOT SCALE DRAWING		REVISION A	
						 ADONI TECH Addl. MIDC, Kodoli, Satara 415004 www.adonitech.co.in			
	NAME		SIGNATURE		DATE	TITLE: JHQ-C-20 POLYURETHANE FOAM CRANE BUFFER - GA			
DRAWN	PARESH ADAVANI				25-09-22				
CHK'D									
APPV'D	PARESH ADAVANI				27-09-22				
MFG									
Q.A						DWG NO.			A4
						AT/GA/JHQC/20			
MATERIAL: PU foam, MS base plate			WEIGHT:			SCALE: 1:10		SHEET 1 OF 1	