





PU BUFFER - BASE PLATE MOUNT



VIEW FROM STRIKER END

Technical Parameters

Buffer diameter	Ø320	mm
Buffer height	400	mm
Stroke (max. deflection)	300	mm
Energy capacity	32.154	kNm
Max. buffer force	675	kN
Base plate	400 sq x 14 thk	mm
Mounting holes	4 x Ø22 on 315 sq	mm
Buffer material	Polyurethane foam	
Base plate material	MS, painted	

NOTES

- General arrangement for customer approval - not for manufacture.
- Dashed line = striker face at maximum deflection.
- Polyurethane (PU) foam buffer, shown in red, bonded to MS base plate; 4-bolt mounting.
- Grooved profile controls the deflection characteristic; groove pattern per Adoni Tech design.
- Operating temperature -20 to +80 °C.
- Selection: www.cranebuffer.com | impactcal.netlify.app

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN MILLIMETERS GENERAL ARRANGEMENT - OUTLINE ONLY DIMENSIONS SUBJECT TO CHANGE WITHOUT PRIOR NOTICE PROJECTION: FIRST ANGLE		FINISH: PU red / plate painted		DEBUR AND BREAK SHARP EDGES		DO NOT SCALE DRAWING		REVISION A		
						adoniTech ADONI TECH Addl. MIDC, Kodoli, Satara 415004 www.adonitech.co.in TITLE: JHQ-C-21 POLYURETHANE FOAM CRANE BUFFER - GA DWG NO. AT/GA/JHQC/21 A4				
	NAME		SIGNATURE		DATE					
DRAWN	PARESH ADAVANI				27-09-22					
CHK'D										
APPV'D	PARESH ADAVANI				29-09-22					
MFG										
Q.A										
MATERIAL: PU foam, MS base plate		WEIGHT:		SCALE: 1:10			SHEET 1 OF 1			